



## A TRUSTED SOLUTION SPANDREL PANELS

Spandrel panels are pre-assembled structural pieces used as separating walls or external gables, typically supplied as part of a structural roof package. Howarth Timber Engineering's spandrel panels are specifically designed and fabricated to complement our range of engineered products and to replace the need for conventional masonry, which is expensive and time consuming to build in-situ. As the composition of Howarth's spandrel panels is based on current robust standards there is no requirement for pre-completion testing.

As with all Howarth Timber Engineering's products, each roof structure incorporating spandrel panels is designed in accordance with the Robust Details certification scheme. Howarth can provide the appropriate design warranty and we are able to fully certify our supply chain in accordance with recognised industry standards.

Howarth Timber Engineering's spandrel panels are loaded vertically or horizontally, as size and configurations allow, onto customised trailers, and delivered to site at pre-arranged dates and times. Once on site the panels will require some form of mechanical off-loading and must be stored vertically. Appropriate lifting and temporary support must be provided at high level to facilitate installation, and Howarth Timber Engineering can provide guidance on load weights and dimensions.





